

FOCAL CONTRACTING Sdn Bhd

T2A-13-02, MENARA 3, JALAN AMPANG

50450, Kuala Lumpur, Malaysia

Tel: +60 3 67381314

Email: sales@fncontracting.com ; md@fncontracting.com ;

Website: <http://www.fncontracting.com>



SAI CT ROAD WORKS (003501517-T)

Date: March 25, 2026

25-1-29 PLAZA PRIMA BATU 4 ½ JALAN

KLANG LAMA, 58200 KUALA LUMPUR.

TEL:0186636014 : EMAIL- saictroadworks@gmail.com

OUR REF: FOCAL200-25/03/2026

SUBJECT: Letter of Award for subcontract of The Construction and Completion of Road Alignment and Drainage Works for RUB 15, RUB 16 and E8 Expressway at Gombak, Section 8

Attn to: Mr. CHALISWARAN A/L VELU

Dear Sir,

We refer to your quotation (SCT260303) ; we are pleased to award you Subcontract of the above project subject to the following terms and conditions: -

1. SCOPE OF WORK

Your scope of work shall be defined as per Bill of Quantities, Specifications and technical data. The standard of work shall be to the entire satisfaction of the main contractor and Your sub-contract work shall comprise the drainage works on the above project as per attached Bills of Quantities.

In addition, you shall be held solely and fully responsible for any consequences due to poor workmanship and all additional cost for rectification works if necessary.

SUMMARY OF BILLS OF QUANTITIES:

Bill NO.	Description	Unit	QTY	Rate (RM)	Total Amount (RM)
1	U Drain; To construct U drain with mass concrete as base to receive block drain; UPVC weepholes with 1 layer of geotextile filter fabric; including all excavation, backfilling, well compaction, disposal of surplus materials and all necessary temporary works in accordance to drawing and specification. (Rate herein shall exclude supply of concrete, BRC and cement). Size 300mm (H) x 300mm (W) Ditto; with size 600mm (H) x 600mm (W) Ditto; with size 750mm (H) x 750mm (W) Ditto; with size 1500mm (H) x 1500mm (W) Ditto; with size 600mm (H) x 600mm (W) with cover slab Ditto; with size 750mm (H) x 750mm (W) with cover slab	m	5291.00	50.00	259,600.00
2	Box Culvert; To fix concrete box culvert with size 1500mm (L) x 1500mm (W) including all excavation, backfilling, well compaction, disposal of surplus materials and all necessary temporary works in accordance to drawing and specification.	m	39	150.00	5,850.00
3	Pipe Culvert; To fix concrete pipe culvert with 600mm diameter including all fittings, spigot, socket joints, bends and all necessary temporary works in accordance to drawing and specification.	m	6	100.00	600.00

FOCAL CONTRACTING Sdn Bhd

T2A-13-02, MENARA 3, JALAN AMPANG

50450, Kuala Lumpur, Malaysia

Tel: +60 3 67381314

Email: sales@fncontracting.com ; md@fncontracting.com ;

Website: <http://www.fncontracting.com>



4	To construct precast concrete or cast in-situ concrete RC Sump ; overall size 1000mm (L) x 1000mm (W); lean concrete under, reinforced concrete, reinforcement bar, steel step; complete with grating all connection to and forming all openings, excavation, disposal offsite, backfilling in accordance to drawings and specifications.	NO.	40	500.00	20,000.00
5	Concrete Drainage Combined ; To construct concrete drainage combined with size 1000mm (W) x 600mm (H) x 100mm thick; lean concrete 10/20, concrete 25/20 with one (1) layer of BRC A6 mesh including all excavation, backfilling, well compaction, disposal of surplus materials, formworks and all necessary temporary works in accordance to drawing and specification.	m	45	50.00	2,250.00
6	Cascade Slope Drain ; To construct cascade slope drain with size 450mm (H) x 300mm (W) x 100mm thick; concrete 25/20 with one (1) layer of BRC A6 mesh including all excavation, backfilling, well compaction, disposal of surplus materials, formworks and all necessary temporary works in accordance to drawing and specification.	m	145	50.00	7,250.00
7	Asphalt Cutting ; To cut existing asphalt road 50-100mm and disposal/removal from site	m	600	10.00	6,000.00
GRAND TOTAL (RM)					301,550.00

NOTES:

- your rates are only based on labour works and inclusive of all Machineries, transportation, worker accommodation, installation, survey, mobilization and demobilization of the equipments and machineries, and other related expenses etc.
- All the prices are excluding of supply of materials such as ready-mix reinforcement concrete, rebars, metal fixtures, BRC B10 Mesh, Precast Drain, precast culvert pipe & box culvert, steel or precast cover, Geotextile fabric, cement, sand etc.

TERMS & CONDITIONS:

- The BOQ quantities shall be re-measurable according to the work done at site.
 - The progress invoice shall be prepared until 15th of each month.
 - Payments shall be made as agreed with 30-40 days of the approved invoice.
 - All payment shall be made to SAI CT ROAD WORKS bank account.
 - The work schedule and other related terms shall be discussed with main contractor in kick off meeting
- Thanking you in advance.

With Regards

Muhammad Faraz Ahmad

Accepted By:

SAI CT ROAD WORKS (003501517-T)

