

PURCHASE ORDER

Ref: Quotation No: SCT26 0514



SUPPLIER:

SAI CT ROAD WORKS (003501517-T)(202303151171)

25-1-29 Plaza Prima Batu 4 1/2 Jalan Klang Lama,

58200 Wilayah Persekutan Kuala Lumpur

TEL - 0186636014, 0192933696 EMAIL- saictroadworks@gmail.com

DATE	PURCHASE ORDER#
12/6/2026	PO-TS-2026-001

DELIVER TO:

TEKTON SOLUTIONS (LA0070354-X)

N3-1-15, USJ 14/1, USJ 14

47630, Subang Jaya, Selangor

TEL - 014-332 8835 EMAIL - tektonsolutions.my@gmail.com

PROJECT SITE:

REGINA RESIDENCE USJ 1

Regina USJ 1, Jalan Subang Permai, USJ 1

47500 Subang Jaya, Selangor

Ref: ROAD RESURFACING WORKS WITHIN VICINITY OF REGINA USJ 1

With reference to the above,:-

NO	DESCRIPTION	RATE (RM)	QUANTITY	AMOUNT (RM)
1	(All quantities are provisional and subject to actual site measurement upon 'completion of works'.)			
	Part A - Site Preparation			
	A2 - Raising up existing septic manhole cover and frame (1.5m x 1.5m) to match new road level, including all necessary adjustments, materials and making good	350.00	3 NOS	1,350.00
	A3 - Raising up existing septic manhole cover and frame (840mm x 840mm) to match new road level, including all necessary adjustments, materials and making good	250.00	12 NOS	3,000.00
	A5 - Cleaning of sand, dust, and debris from entire work area using bobcat with broom attachment, including disposal of waste materials	L/SUM	1	2,800.00
				7,150.00
2	Part B - Road Works			
	Supply and lay one layer of tack coat bitumen SK 1 at specified temperature and rate to ensure strong adhesive bond between layers	1.20	4,517 m2	5420.40
	Supply and lay premix asphaltic concrete wearing course 10mm aggregate size, minimum 50mm compacted thickness, including all materials (ACWC 14 Premix aggregates), machinery (backhoe, back pusher, roller), skilled labour, traffic management, transportation and completion to specified levels and grades.	30.00	4,517 m2	135,510.00
	Supply and application of thermoplastic road marking paint for single directional arrow signs , including surface preparation, heating equipment , and application to standard dimensions and specifications.	75.00	14	1,050.00
	Supply and application of thermoplastic road marking paint for double directional arrow signs , including surface preparation, heating equipment , and application to standard dimensions and specifications.	90.00	4	360.00
	Supply and application of road marking paint for parking lot bay markings (standard car park size/ follow existing car park size), numbering, including line marking, surface preparation and completion	20.00	80	1,600.00
	Supply and application of parking lot numbering using durable road marking paint or thermoplastic material , numbers to be clearly visible and of standard size	5.00	80	400.00
				144,340.40
		TOTAL	RM151,490.40	

Thank you and Best regards,

ANDREW KUMAR

MANAGING DIRECTOR

